ORDINANCE NO. 35
OF THE
BOARD OF SUPERVISORS OF
THE TOWNSHIP OF EAST NORRITON
Montgomery County, Pa.

REGULATING THE DUTIES OF REGISTERED PLUMBERS MAKING SEWER CONNECTIONS, REQUIRING PLANS FOR COMMERCIAL AND INDUSTRIAL PROPERTIES OR IN SPECIAL CONDITIONS, PERMITS, INSPECTIONS AND APPROVALS, STANDARDS OF MATERIALS, INSTALLATION REGULATIONS, PRESCRIBING PENALTIES.

The Board of Supervisors of East Norriton Township do hereby ORDAIN and ENACT as follows:

Section 1. No person required to connect to the East Norriton Township sewer system shall make or provide for such connection except in compliance with the terms of this ordinance.

Section 2. All persons required to connect to the East Norriton Township sewer system shall obtain the services of a Registered Plumber as set forth under Ordinance No. 29 of said Township or it's amendments.

Section 3. All registered plumbers qualifying under Ordinance No. 29 aforesaid, shall make sewer connection installations in strict compliance with the terms of this ordinance as follows:

A. Permits - Inspections - Fees.

Registered Plumbers shall obtain a permit from the said Township for each property required to connect to the sewer system and a permit fee and inspection fees shall accompany each application therefor. The amount of the permit fee and inspection fees shall be determined and fixed by resolution of the Township supervisors as from time to time may be reasonable and necessary.

B. Plans and Specifications.

Plans and Specifications prepared by a Registered Engineer may be required in duplicate with the applica-

tion for permit for sewer construction on commercial and industrial properties or when required for special conditions by either the Township or the East Norriton Township Municipal Authority.

C. Inspection and Approval. C&SC

The Plumber shall notify the Inspector appointed by the Township prior to the starting of any work and prior to backfilling. The Plumber shall have approval of the installations by the Inspector before putting the sewer in use.

D. Materials. C&SC

(a) Vitrified clay pipe sewers shall be of best quality, standard strength, hard-burned, salt glaze, vitrified clay pipe. Pipe shall conform to ASTM designation C 13-57 T. The jointing materials for vitrified clay pipe shall be precast as manufactured under the trade name of "Tylox type B", "Wedge-lock", or "Presto-seal". All vitrified clay sewer pipe shall be five (5) inch diameter.

(b) Castiron soil pipe shall be extra heavy castiron (sixty (60) pound per five foot length) or medium weight centrifugal spun (forty-five (45) pound per five foot length). Cast iron pipe shall be four (4) inches in diameter.

(c) Joint packing shall be of the best quality hard-twisted hemp. Unless otherwise permitted by the Engineer, all packing material shall be not less than one-half ($\frac{1}{2}$) inch size. Lead used for filling bell and spigot joints shall be of the best quality soft pig lead, suitable for caulking and securing tight and permanent joints, and shall conform to the requirements of Fed. Spec. QQ-L-156, Type I.

E. Installation. C/SC

All installation shall be true to line and grade and having a grade of not less than one-quarter inch per foot. Changes in direction shall be accomplished by 90° long sweeps. A horizontal intercepting vented trap shall be provided and installed and is to be located not less than five feet outside the legal right-of-way line of the street. The vent shall be four inch castiron and extend six inches above the surface of the ground with a cast-iron vent cowl attached.

If the length of the building sewer exceeds 125 feet from the vent to the building, standard cleanouts must be provided for changes in horizontal direction. Minimum earth cover for the sewer shall be thirty (30) inches.

Cellar floor or ground floor drains will not be permitted to connect to the sewerage system. The bed for the pipe shall be firm and shaped to the bell and hub of the pipe.

If ground water is encountered during construction, this water shall be pumped away from the site of construction and not be permitted to run through the sewer lateral during construction.

Backfilling shall be accomplished by hand tamping from the bottom of the trench to a minimum of six (6) inches above the bell of the pipe. If the trench excavation is made too deep, it shall be backfilled to the proper grade with No. 1 stone and thoroughly compacted.

In unstable ground conditions, concrete cradle may be required for soil bearing. If concrete cradle is required, the concrete shall be two thousand (2000) pound test.

If ground water is encountered, a crushed stone under drain may be required.

Section 4. Penalty. - Any person, partnership or corporation who or which shall violate any of the provisions of this Ordinance or the regulations adopted hereunder, shall upon conviction thereof, forfeit and pay a fine of not less than Twenty-five Dollars ($25.00), nor more than Three Hundred Dollars ($300.00), to the Township of East Norriton, the same to be collected by summary proceedings brought in the name of the Township before any justice of the peace in said Township. Each 90-day period during which such violation of such provisions shall continue, shall be deemed to be a separate offense.

Section 5. If any provision, sentence, clause, section or part of this Ordinance or the application of any provision hereof, is for any reason found to be unconstitutional, illegal or invalid, such unconstitutionality, illegality or invalidity shall not affect or impair any of the remaining provisions, sentences, clauses, sections or parts of this Ordinance. It is hereby declared as the intent of the Board of Supervisors that this Ordinance would have been enacted had such unconstitutional, illegal or invalid provision, sentence, clause, section or part not been included herein.

Section 6. All ordinances or parts of ordinances in conflict, or inconsistent herewith, be and the same are hereby repealed absolutely.

DULY ENACTED AND ORDAINED this 9th day of January, 1961.

HENRY K. STANDBRIDGE

Chairman - Board of Supervisors

(TOWNSHIP SEAL)

ATTEST:

CALVERT V. HURDLE

Secretary